



MACON
MUNICIPAL
UTILITIES

Bid Packet
Jackson Street
Sanitary Sewer Line
Installation
Bids Due:
Wednesday, July 14, 2021

Macon Municipal Utilities is requesting bids for the installation of Sanitary Sewer Service to properties in the 600 Block of Jackson Street in Macon, Missouri. This project consists of approximately 460 linear feet of 8" PVC sewer main, 1- 48" Manhole, approximately 230 linear feet of 4" PVC Sewer Service lines, 6- 8"x4" tees for sewer taps, 6- 4" cleanout assemblies (double or single Uni-directional), abandonment of 6" PVC in existing manhole and rebuild channel in existing manhole. Bids are to be delivered to the MMU Business Office at 106 W. Bourke Street, Macon, MO 63552 by **1:00 pm on Wednesday, July 14, 2021.**

Successful bidder must purchase a City Business License. This License may be obtained from the office of the City Collector located at 106 W. Bourke Street, Macon, MO. 63552. The fee is \$50.00.

Successful bidder is requested to carry insurance coverage for the duration of the project in the following amounts. Lower coverages may be accepted.

- **\$1,000,000 Liability**
- **\$2,000,000 Aggregate**
- **\$5,000 Medical**
- **Workers' Compensation**

The successful bidder will be required to provide a certificate of insurance listing Macon Municipal Utilities as additional insured, and sign a hold-harmless agreement. Successful bidder shall require same of all subcontractors. Each bidder must inform himself fully of the conditions relating to the composition of the project and the employment of labor thereon. Failure to do so will not relieve the successful bidder of his obligation to furnish all material and labor necessary to carry out the provisions of this project.

Submission of bid confirms bidder agrees that they understand, and agree to abide by all terms and conditions, responsibilities and specifications of the project. Bidder will be presumed to have inspected the site and to be thoroughly familiar with the project requirements. The failure or omission to do so, shall in no way relieve any bidder from any obligation in respect to his bid.

Bidders are informed that pursuant to Section 285.530, RSMo, as a condition of the award of any contract in excess of five thousand dollars (\$5,000), the Bidder shall, by sworn affidavit and provision of documentation, affirm its enrollment and participation in a federal work authorization program with respect to the employees working in connection to the contracted services. Bidder shall also sign an affidavit affirming that it does not knowingly employ any person who is an unauthorized alien in connection to the contracted services.

This project is not expected to be subject to **prevailing wage** rates. Once work has commenced, the work shall be continuous and the contractor shall not remove their personnel and/or equipment from the City until the work has been completed and approved by City personnel.

The bidder's attention is directed to the fact that all applicable State Laws, Municipal Ordinances, and the rules and regulations of all authorities having jurisdiction over composition of the project shall apply to the contract throughout, and they will be deemed to be included in the contract the same as though herein written out in full.

Macon Municipal Utilities shall be the final judge of the quality and suitability of the work, materials, and methods of construction for the purposes for which they are used. Should they fail to meet approval they shall be forthwith reconstructed, made good, replaced, and or corrected by the contractor at his own expense. Rejected materials shall be removed immediately from the site.

Macon Municipal Utilities reserves the right to reject any or all bids. Please see the next page for project specifications and bid tab.

PROJECT SPECIFICATIONS

The intent of this project is to provide Sanitary Sewer Service to Properties in the 600 Block of Jackson Street in Macon, Missouri. This project consists of approximately 460 linear feet of 8" PVC sewer main, 1- 48" Manhole, approximately 230 linear feet of 4" PVC Sewer Service lines, 6- 8"x4" tee's for sewer taps, 6- 4" cleanout assemblies (double or single Uni-directional), abandonment of 6" PVC in existing manhole and rebuild channel in existing manhole. The existing sewer consists of service laterals tying into service laterals and running across neighboring properties. This project will consist of installing new Sanitary Sewer manhole, Sanitary Sewer main, tying into existing manhole and tying in service laterals with cleanout assemblies at customer's property. Trace wire is required with main and laterals, to be brought up at manholes and cleanouts. Rock will be provided at Macon Municipal Utilities Yard and area will be provided for disposal of fill. Construction area is to be brought back to grade, rock installed in street and drives. Macon Municipal Utilities will be responsible for concrete replacement and final dress-up. New main will be installed at 0.40ft / 100ft slope.

Bid Tab:

<u>Item #</u>	<u>Description</u>	<u>Units</u>	<u>Est. Qty.</u>	<u>Unit price</u>	<u>Total</u>
1	8" SDR 35 PVC Pipe, Installed Complete	LF	460		
2	4' Diameter Sanitary Manhole, Installed Complete Depth of New Manhole Approximately 6'6" Depth of Existing Manhole is 8'	EA	1		
3	Service Line Connection, Including 8"x4" Tee & Fittings SDR 35, Installed Complete	EA	6		
4	4" SDR 35 PVC Service Line, Installed Complete	LF	230'		
5	Cleanout Assembly, Installed Complete	EA	6		
6	Connect to Existing Manhole & Removal of Existing 6"	EA	1		
7	# 12 AWG Solid Tracer Wire	LF	800'		
8	Labor for Installation				
				Total	

Bidder: _____

Contact Info: _____

The contractor shall, before any work is accepted by Macon Municipal Utilities, remove from the job site all litter and trash of any kind, and shall leave the area in good condition and ready for its use.